
# Plan Reviews and the Illinois Urban Manual

Candice Jacobs, CPESC Resource Conservationist Kane-DuPage SWCD

### Where are we...



- Northeastern Illinois
- Kane and DuPage Counties
- 50 miles west of Chicago and the Lake Michigan coast.
- Fall within the
   Jurisdiction of the
   Chicago District of the
   US Army Corps of
   Engineers

## Section 404 – Clean Water Act

### Dredge/Fill Permitting


Section 404 of the Clean Water Act established a permit program to regulate the discharge of dredged or fill material into waters of the United States. The program's scope also includes the regulation of discharges of dredged or fill material into wetlands adjacent to national wetlands. This permit program is administered by the Secretary of the Army through the U.S Army Corps of Engineers.

## Interagency Cooperative Agreement

- KDSWCD agrees to:
  - Use technical references
  - Review Plans for SESC
  - Attend Pre-Cons
  - Conduct Inspections
  - PrepareCorrespondence
  - Consult with contractors

- USACE agrees to:
  - Will require the permittee to submit to KDSWCD
  - Request SWCD to comment on plans
  - Request SWCD to perform site inspections

## The Corps Permit



Corps permit is not completed until our review is complete.



#### DEPARTMENT OF THE ARMY

СРОССО ОНЯТИЛИ, ОППРА В Е БОЗВИВЕНО ПП ИОМИН САМА, ВОЖЕВО ОРИСЛОС, ЧЕЛИОС ООМЕТОР

February 11, 2010

Technical Services Obvision Regulatory Branch LRC-2013-68670

STRIPECT: Soft Ecosion and Sediment Control Plans by Eldridge Park Lagona Tessio Ruphresmond to Soft Creek in the Village of Elashurgt, DuPlage Coursy, Ritmost



The U.S. Authy Corps of Engineers, Chicago District, has received your notification for influences need to Regional Permit Program and has assigned \$300-2010-80006 up for reference consider. This consider will be used on all follow correspondence expecting your notification.

Following a profinsionary evaluation of your project, the District has determined that your project's soil crowing and audiescal control plans shall be reviewed by the County Soil and Water County of the County Soil and Water Co

Konei/SePage SWCD After Condition Joests 2313 Octor Street St. Charles, H., 94173 (600) 584-7962

Please contact the SWCD as soon ay providing to obtain information on the application process required to surface your plans. The submission of your plane in this agency and a determination that these most technical stundards by required in accordance with Canadai Condition of of the Regional Paradit Program.

You see advised but to undertake any activity in contention with the propagation obtivity in any votus of the fluided States world suffering times under the RPP has been obtained. Any work acted to the proposed project endortakes on splane is some so of your year risk and with not projudice the processing of your meditionion.

Throughout the duration of construction activities, you shall adhere to all soil erosion and sediment control measures determined to meet technical standards by the Kane/DuPage SWCD.


## The Plan Review

## The Process - Plan Review



## Plan Review - Some Research

- Digitize the Parcel
- Check for Water Features/Critical Areas



## Plan Review Checklist

SESC FILE #:	SESC FILE #:
REVIEWED BY:	REVIEWED BY:
INTERNAL SESC PLAN REVIEW CHECKLIST  ☐ if already present on plans ☐ if needed on plans ☐ if needed on plans ☐ if not applicable to project  ☐ Standard Notes ☐ Replace straw bales with alternative measures ☐ Inspection and Maintenance Scheduleonce/week or after ½" rain event ☐ Soil Stabilization ☐ Minimization of disturbed area ☐ Soil Stabilization Chart Meets IUM standards ☐ Seeding Rates and Mulch Application - Meets IUM Standards ☐ Temporary Seeding—In areas left idle for more than 14 days. ☐ If Kane County see note from ordinance on stabilization within 7 days ☐ Permanent SeedingAll disturbed areas shall be stabilized within 14 days of final grading ☐ Winter PreparationWinter shutdown shall be addressed early in the fall growing season so that slopes and other bare earth areas may be stabilized with temporary and/or permanent vegetative cover for proper erosion and sediment control.	All outlets should be stabilized  Riprop aprons should be sized appropriately  Provide a detail with apron dimensions and stone sizes  Filter fabric is to be installed beneath all riprap
□ Slope Protection—protect slopes with seeding and straw mulch w/netting or erosion control blanket     □ Methods for conveying offsite and onsite runoff through the site     □ Stabilized channels	Address how creek/wetland crossings are to be handled (harrative and detail)  Once work in these areas begins, priority shall be given to the
☐ Ditch checks ☐ Velocity Minimization ☐ Limit slope lengths ☐ Ditch Checks ☐ Surface Roughening	completion of the work and final stabilization of all disturbed areas  Stabilization at the end of each day  Isolate Work Area from concentrated flows or stream flow  Dewatering method  Sump pit
□ Stockpiles □ Location shown on plans and not to be located near critical areas □ If stockpile to remain in place more than three (3) days, erosion and sediment control measures to be provided □ If stockpile to remain in place more than thirty (30) days, temporary seeding is required	Outlet hose placement Outlet hose treatment Details for each practice used with all required values filled in Review Comments:
☐ Inlet Protection—note and/or called out on plans ☐ Culvert Inlet Protection at outfall of Stormwater facility ☐ Stand Pipe or Perforated Riser	
☐ Tracking onto streets	

# Where do our Technical Standards come from?


- IL Urban Manual
- Our County Technical Manuals
- Other States Technical Manual
- Manufacturers Specifications
- Past Performance of Practices EXPERIENCE!

## Plan Review – Key Components


#### Standard Notes:

- Unless otherwise indicated, all vegetative and structural erosion and sediment control practices will be constructed according to minimum standards and specifications in the Illinois Urban Manual latest edition.
- ➤ The Kane-DuPage Soil and Water Conservation District (KDSWCD) must be notified one week prior to the pre-construction conference, one week prior to the commencement of land disturbing activities, and one week prior to the final inspection.
- A copy of the approved erosion and sediment control plan shall be maintained on the site at all times.
- Prior to commencing land-disturbing activities in areas other than indicated on these plans (including but not limited to, additional phases of development and off-site borrow or waste areas) a supplementary erosion control plan shall be submitted to the owner for review by the KDSWCD.
- ➤ The contractor is responsible for installation of any additional erosion control measures necessary to prevent erosion and sedimentation as determined by the KDSWCD.
- > During dewatering operations, water will be pumped into sediment basins or silt traps. Dewatering directly into field tiles or stormwater structures is prohibited.
- Also, please add note to state that, "It is the responsibility of the landowner and/or general contractor to inform any sub-contractor(s) who may perform work on this project, of the requirements in implementing and maintaining these erosion control plans and the National Pollutant Discharge Elimination System (NPDES) permit requirements set forth by the Illinois EPA."


## Perimeter Silt Fence



#### SILT FENCE PLAN



#### ELEVATION



#### FABRIC ANCHUR DE I

#### NOTES


- Temporary sediment fence shall be installed prior to any grading work in the area to be protected. They shall be maintained throughout the construction period and removed in conjunction with the final grading and site stabilization.
- Filter fabric shall neet the requirements of naterial specification 592 Geotextle Table 1 or 2, Class I with equivalent opening size of at least 30 for nonwoven and 40 for woven.
- Fence posts shall be either standard steel post or wood post with a minimum cross-sectional area of 3.0 sq. in.

Date
Bate Bate Bate
Dote .



STANDARD DVG. ND. IUM-620A

SHEET 1 OF 2 DATE 3-16-12



ENCING (DOUBLE


30' BUFFER TEMPORARY EROSION

CONTROL BLANKET (NORTH AMERICAN


WRAP WETLANDS)

## -Erosion Control Blanket Location

Rock Lined Aprons at FES



## Concrete Washout



### Location

– Makecertain notnext tostormwaterfacility



### **Inlet Protection**

PRACTICE STANDARD

#### INLET PROTECTION – PAVED AREAS

(no.) CODE 861



Source: AISWCD







Inlet protection using fabric only as a drop-in shall not be allowed.

## Check Dams

- Rock Checks
- Manufactured ditch check







## Dewatering Notes

During dewatering operations, water will be pumped into sediment basins or silt traps. Dewatering directly into field tiles or stormwater structures is prohibited.

perfecting already into held these of stoffmatter strategies is profibited.

ILLINOIS URBAN MANUAL PRACTICE STANDARD

#### **DEWATERING**

(no.) CODE 813



(Source: Illinois Urban Manual Technical Committee)



7. WATER PUMPED DURING CONSTRUCTION OPERATION SHALL BE FILTERED.

## The Process - Plan Approval

### 1. Approval Letter,

- Plans Meet Technical Standards
- Site Inspections
- 2. Stamped Plans,
  - File number
  - Signature
- Mail Out:
  - Save to File
  - Corps/Municipality
  - Contractor/Owner

Kane – DuPage Soil & Water Conservation District



February 27, 2013

Name Address Address

Corps Number: LRC 0000 00 000 KDSWCD File: 13e000

Approved Plan Set Dated: mm/dd/yy

Dear Name:

I received your revised soil erosion and sedimentation control plan submittal for the project located in Wheaton, Illinois. Thank you for incorporating our comments into the plan, it will improve the quality of protection for the natural resources, both on and off site. This letter and a set of stamped plans located at the construction office on site, will serve to certify that the erosion and sediment control plans meet Technical Standards.

I will visit the site several times during the course of construction to assess compliance with the specifications and will be glad to address specific issues that may arise during the course of construction.

Sincerely.

Candice Jacobs, CPESC Resource Conservationist

Kane-DuPage Soil and Water Conservation District

ECC: Project Manager, USACE

2315 Dean Street, Suite 100

St. Charles, Illinois 60175

(630) 584-7961x3

Fax: (630) 584-9534

www.kanedupageswed.org

### Planning and coordination allow us to...



...help prevent this!